BILL OF QUANTITY

Name of Work: Supply, Installation Testing and commissioning of Split AC in newly build up extension part of the IITG hospital

SI No	Description	Unit	Qty	Rate (₹)	Rate in figure	Amount (₹)
	Part A : Supply of AC					
1.0	2 TR 5 star rated Split Inverter type room Air Conditioner (For Cooling) having Rotary -R410a/R32 Compressor, Power supply 230V AC, 50HZ, Power Input:1600W or less, Running current :7.3 amp or less, Speed setting (Cooling/Fan): 4/3, also having features of LDC Remote Operating Control, Electronic Thermostat, Oscillating Lovers, auto air swing, Auto Start, ON/OFF timer, Dehumidification, Sleep mode etc	No	6.0			
	Part B : Installation of AC					
2.0	4 KVA Voltage Stabilizer, I/C wiring IDU & ODU	No	6.0			
3.0	Starter Switch	No	6.0			
4.0	Communication Cable beyond 4 meter length	No	18.0			
5.0	Clamp for Outdoor Unit Fitting	No	12.0			
6.0	Copper beyond 4 meter length	meter	30.00			
7.0	Drain pipe 25mm dia CPVC	meter	30.00			
8.0	Installation Charges for Items 1 to 7 as above	No	6.00			
	Total Amount =					
	Discount@%, if any =					
	Net Quoted Amount =					
	Say =					
(Rupeesonly)						