

Bill Of Quantity

Name of work: Supply and Installation of MS street light pole in the existing location from Main gate to Joyguru road

Sl. No	Description of Item	Unit	Qty.	Rate (₹)	Rate in words	Amount (₹)
1	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required					
	i) Above 8.0 metre and upto 10.0 metre	nos.	4			
2	Supply and installation of 10mtr long SP 44 MS tubular make Nezone or equivalent	nos.	3			
3	Supply and Installation of SMC junction Box of Size 295mm x195mmx100mm (make Sintex/Hansel	nos.	4			
4	Supply MS bracket suitable for existing street light with applying a priming coat of approved steel primer using structural steel etc as required	mtr	3			
5	Supply of 90W PDC LED street light aerodynamically designed with better thermal housing comprised of separate lamp housing of IP65 complete with all accessories as required to provide energy efficient lighting for outdoor	nos	8			
6	Supply of following types of voltage grade up to 1100V PVE insulated round sheathed unarmored multicore cable make polycab/ KEI/Finolex /RRKabel/Havells or equivalent					
	i) 3C, 2.5 sqmm wire	mtr	70			

7	Installation of ,testing and commisioing of LED street light fittings on existing pole etc complete as required.(Including making of Bamboscaffolding)	nos	8			
8	Considering deimentaling and uprooting of existing street light pole with light fittings complete as required	nos	1			
	TOTAL AMOUNT =					
	Discount @.....%, if any =					
	Grand Total Amount =					
	<i>(Rupees only)</i>					

N.B: Quoted rates should be inclusive of delivery/service at site including loading, unloading, supervision, testing, transportation etc.

Place:

Date:

Seal & Signature of Tenderer