BOQ

for

Name of Work: MISC-Electrical works at Subansiri Hostel in IITG Campus.

NIT No: IITG/IPM/NIT/FY22-23/44; Dtd-11/01/2023

SI. No.	Description of Item	Unit	Qty.	Rate (in Rs.)	Rate in Word	Amount (Rs.)
1.0	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.					
	a). 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	Mtr	250			
	b).2 X 4 sq. mm + 1 X 4 sq. mm earth wire	Mtr	275			
2.0	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed Conduit as required.					
	a). 25 mm	Mtr	385			
	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
	a). 15/16 A switch	Each	12			
3.0	b). 5/6 A Switch	Each	25			
	c). 6 pin 15/16 A socket outlet	Each	12			

	d).3 pin 5/6 A socket outlet	Each	25					
4.0	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.							
	a). 4 Module (125mm X 75mm)	Each	37					
5.0	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.							
	a). Single pole	Each	12					
TOTAL AMOUNT								
(RupeesOnly)								

N.B: Quoted rate should be inclusive of all Taxes.

Place:

Date:	Seal & Signature of Bidder
Date.	Scal & Signature of Blader