

BOQ

NIQ No- NIQ IITG/IPM/NIQ/FY25-26/04 dated 22.07.2025

Name of work: Trilingual outdoor signage for all Hostels of IITG Campus

	Item	unit	Qty	Rate	rate in words	Amount
1	Supply ,Cutting, fixing of Retro Reflective on Vinyl for outdoor signage(thickness min 128 microns)	SQFT	480			
2	Supply ,Cutting , fixing of ACP Board thickness 4 mm	SQFT	240			
3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : 13.61.1 Two or more coats on new work	SQM	102			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) 4.1.5	CUM	1.5			
5	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. 10.25.2 In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	KG	900.0			
6	10.28 Providing and fixing stainless steel (Grade 304) made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in charge,	KG	20			
	Total					
	GST @18%					
	Grand Total					