

## CORRIGENDUM : 1

### REVISED BILL OF QUANTITIES

Name of Work: "Raising of height of Table tennis room floor at Kapili Hostel at IITG Campus".

Item no.	Description of Items	Unit	Quantity	Rate in ₹		Amount (₹)
				in figure	in words	
1.	Providing and casting brick bat mortar in proportion 1:5:10 (1cement : 5 sand : 10 brick bat of size 40mm average)	Cum	10.00			
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	8.00			
3.	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., complete.	Sqm	80.00			
	Total					
				Rebate if any in.....% =		
				Total after rebate =		

Seal



(Signature of the tenderer)