

**BOQ**  
for

<b>Name of Work: Additional light point wiring for 82 rooms at Dhansiri Hostel in IITG Campus.</b>						
<b>NIT No: IITG/IPM/NIT/FY22-23/33; Dtd-11/11/2022</b>						
<b>Sl. No.</b>	<b>Description of Item</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate (in Rs.)</b>	<b>Rate in Words</b>	<b>Amount (Rs.)</b>
1.0	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.					
	Group A	Pt	82			
2.0	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed Conduit as required.					
	a). 25 mm	Mtr	574			
3.0	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
	a). 5/6 amps switch	Each	82			

4.0	Installation, testing and commissioning of pre-wired,fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc. directly on ceiling/ wall, including onnections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	Each	82			
5.0	Supply of 20watt LED batten Light alongwith all accessories. (Make-Syska/Philips/bajaj/havells/CG)	Each	82			
<b>TOTAL AMOUNT</b>						
Discount@.....%, if any						
<b>GRAND TOTAL AMOUNT</b>						

(Rupees.....)

**N.B: Quoted rate should be inclusive of all Taxes.**

**Date:**

**Place:**

**Seal & Signature of Bidder**